

Optimization of Emissions Reduction Equipment (SCR)

Jeff Williams

SmartProcess

Business Development Manager

Where **i**deas become **solutions**.



Presenters

- Jeff Williams
- John Hayden



Where **ideas** become **solutions.**



Agenda

- Overview
- SCR Optimization
- SCR project Case study

Where **ideas** become **solutions**.



Availability

- Reduced Tube leaks
- Less EFORS from sootblower problems

Environmental Management

- NO_x / SO₂ cap compliance
- NO_x / CO / CO₂ minimization
- Opacity Reductions

Generation Management

- Fleet / Economic Evaluation
- Real-Time Performance
- Heat Rate Improvements
- LOI reductions

Operational Flexibility

- Dispatch Response
- Ramp Rate Improvements
- Start-up guidance


History - Of SmartProcess Performance and Optimization Experience – Post 1990



Low NOx Dispatch system for LADWP



Power Industry first multivariable advanced fuzzy logic feedforward model based steam temperature control




Developed and Beta Tested First Immunological Self-Learning system – Patent Pending

Embedded Model Based Control in Ovation® expert control system via APC.


Steam Temperature LDC



First Dynamic state space models with neural network component – NeuCOP from NeuralWare – Later Aspen




Acquired By Emerson
Named Power Industry Center of Excellence for Emerson



Power Industry first software based intelligent sootblowing combining expert system and neural networks

Industry First Object based Plant performance tool




Industry First Cyclone Boiler Optimizer



SmartProcess powers ISA/POWID facility of the year



Released first browser based interface
SmartEngine




Industry First Fleet wide optimization using portal technology
EXCHANGE

Where ideas become reality

SmartProcess Firsts For Power

- 1st Dynamic Combustion Optimizer
- 1st Advanced Steam Temperature application
- 1st Intelligent Sootblower Optimizer
- 1st OPC based Performance Monitor (GPA)
- 1st Cyclone Optimizer
- 1st Fleet Optimizer
- 1st Open Web Enabled Economic Optimizer, Combustion Optimizer, and Intelligent Sootblower

Solutions for Improved Plant Performance



Complete system

Site Assessment

Model Design & Validation

Project Start

Installation of Model

Development of Plant Integration Plan
and Design of control modifications

Advisory Mode Operation

Execution of Plant Integration Plan

Closed-Loop Mode Operation

Data Collection & Conditioning

Benchmark & Documentation

Where **i**deas become so

 **SmartProcess**®

Combustion Optimizer

SP_0078
November 2005




SCR Optimizer

The SCR Optimizer evaluates data to control the ideal inlet temperature and ammonia usage that will reduce NOx emissions and slip.

Take your SCR technology a step further.


■ Results

- Improves efficiency
- Maintains optimum temp
- Extends 1st stage catalyst life




SCR Optimization Factors

- SCR's operate most efficiently at 600-670°F
- There are a number of layers
- Excess ammonia spray saturates the catalyst bed and escapes the reactor (slip)
- NOx inlet variability causes uneven reactions



SCR Optimization

- Control temperature via Bypass and O₂ bias
- Minimize NO_x variability
- Model reactor, predict flow requirement for zero slip



Where **ideas** become **solutions**.

SmartProcess® Improves Emissions and Temperature Control at CPSG's Brandon Shores Power Station



Application

Unit #1 a 680-megawatt coal-fired generating unit with a B&W boiler and GE turbine

- CHALLENGE
 - Optimize temperature control
 - Reduce emissions of NOx
 - Improve ammonia utilization and reduce slip
- SOLUTION
 - SmartProcess SCR Optimization
- RESULTS
 - 120 hour improvement in 90% removal rate hours
 - 250 tons of additional NOx reduction
 - Minimize the impact of varying conditions of coal quality, cleanliness of boiler, mill selection, and daily operation levels

Where **ideas** become **solutions**.



Case Study

SCR Temperature Optimization Project



Where **i**deas become solutions.



Plant Information & History


- **375 Acre Site**
- **Two 680 MW (Gross) Coal Fired Units**
- **5000 to 6000 tons of coal burned per typical day per unit. Delivery by barge.**
- **400-500 tons fly ash per day produced per unit. Fly ash reuse by ProAsh.**
- **Selective Catalytic Reduction (SCR) for NOx control.**
- **167 Employees including Coal and Ash Handling shared with Wagner Plant.**
- **Air Quality Control System Project (Sorbent Injection and Baghouse for Hg and SO3 control, Wet Scrubber for SO2 control) under way to meet Healthy Air Act Requirements Jan 1, 2010.**
- **Unit 1 commissioned in 1984 – GE Turbine & B&W Boiler.**
- **Unit 2 commissioned in 1991 – GE Turbine & B&W Boiler.**



Where **i**ideas become solutions.



Boiler Design




Hot-side Precipitator located before the Air Heaters
Where ideas become solutions.

Types of Coal and Unit Operation


Coal

- Low Sulfur Eastern Bituminous Coal and/or Synfuel (mined in Kentucky / West Virginia)
- Russian
- Other Foreign Coals As Requested by



Operation

- Day: high load regulation - 680
- Night: lower loads – 550 and below



Ozone Season – May to September


Rules:

- **SCR Design is 90% NO_x Reduction (Diff. Between SCR Outlet and Inlet NO_x)**
- **Minimum Desired SCR Inlet Temp. = 585° F (can achieve 90% NO_x reduction at or above this temp.)**
- **Minimum Inlet Temp. = 555° F (if temp. drops below, ammonia flow ceases)**
- **Maximum Economizer Outlet Temp. = 680° F (limitation is ductwork expansion joint material)**
- **Ammonia Slip < 5 ppm (measured at SCR Outlet)**
- **Temperature controlled by combination of economizer bypass dampers and economizer outlet dampers**


NOx Reduction Capabilities

Overfire Air:

Used to reduced inlet NOx down to 0.4 lb/mmBtu




SCR:



Expected NOx Reduction: 90%
(Delta between inlet & outlet NOx)

SCR Systems




Located on the hot-side of the boiler after the hot-side precipitators.

Installed in 2001 to reduce NOx

Where **ideas** become **solutions**.




The SCR Design



The SCR design mandates a minimum inlet flue gas temperature of 555 degf to keep the SCR's in-service. An economizer bypass system, which was part of the initial design, allows flue gas to bypass the economizer section of the boiler and then "re-mix" with the economizer outlet flue gas to increase overall flue gas temperature to the SCR. Some temperature is also lost as the gas passes through the precipitator (see details on next slide).

Where **ideas** become **solutions**.

The Problem



After installation of SCRs and for several years following, Brandon Shores struggled with standard DCS controls to maintain this minimum SCR inlet temperature during ozone season mainly due to the heat loss experienced across the precipitators and limitations of the standard DCS control strategies. When the SCR inlet temperature goes below 555 degf, the SCR ammonia system in the SCR automatically trips off and all NOx emissions are sent directly to stack which results in a high cost to the utility.

Where **ideas** become solutions.



Before This Project

Solution:


- Control the SCR Inlet Temperature using the Economizer Bypass Damper and Economizer Inlet Damper
- Use Economizer Remix Temperature as Feed-forward

Results:

- The base controls would go into a “Hunting” mode unexpectedly. The bypass damper would continually move from 0-100% (trend on next slide)
- The SCR inlet temperature lagged behind the economizer remix temperature significantly.
 - Controlling the SCR inlet temperature was difficult.
 - A change in the remix temperature could take up to 90 minutes to fully realized in the SCR inlet temperature
 - Low SCR inlet temps (due to low loads) tripped the ammonia system. This resulted in a large cost impact due to higher NOx.
 - SCR inlet temperature below 585° F results in less than optimum SCR performance (SCR Catalyst is most effective between 585° F & 600° F)

Overall there were design problems with the original base DCS controls

Damper Swings



Where **ideas** become solutions.



Combustion Optimization Ruled Out

Why?

- **Burner Register Controls are Manual.**
- **No DCS feedback regarding burner register positions.**
- **The flyash quality is constantly monitored by flyash processing facility and must be maintained at all times (process cannot handle large fluctuations in LOI).**
- **Prior attempt to manipulate combustion via a Neural Network was unsuccessful.**

Emerson SmartProcess




In 2006, Constellation contracted Emerson Process Management Power and Water Solutions to provide an optimization system to first study the boiler design and provide an optimization system to optimize the SCR inlet flue gas temperature using a combination of advanced DCS control structures and a fuzzy neural model based optimization system.

Where **i**deas become solutions.



Goals of Project

- Improve Base Ovation DCS Controls at Higher Loads for More Consistent Economizer Remix Temperature and SCR Inlet Temperature



- Add Optimization of Ammonia Dosing to SCR Unit

Where **ideas** become **solutions**.

Part #1

New DCS Base Temperature Controls Design



New Ovation DCS Base Remix Temperature Controls Design

- Ovation DCS is Now Controlling Economizer Remix Temperature by Using the Economizer Bypass Damper and Economizer Outlet Damper (rather than attempting to control SCR inlet temp).
- Control Structures Use Bypass Damper First Then Begin to Use the Economizer Outlet Damper When Bypass is Fully Opened and Remix Temperature is Below Setpoint
- SCR Inlet Temperature is More Consistent/Predictable as a Result of the Better-Controlled Remix Temperature
- Base Full Load Remix Temperature Setpoint is ~ 600° F
- Remix Temperature Must Not Exceed 680° F Due To Precipitator Issues
- Remix Temperature Setpoint Slides to ~600° F as Load Decreases
- 600° F is Minimum Setpoint

Graphic Changes for the new Temperature Control Design

| W2 | | | | | |
|--|----------------|----------------|------------------|-----------------|-----------------|
| <input checked="" type="checkbox"/> toggle | Page | | | | |
| LDC | UNIT MASTER | DRUM TEMP | REHEAT SPRAYS | ATTEMP SPRAYS | AUX STEAM |
| 21A/22A HEATER | 21B/22B HEATER | 23 HEATER | 24 HEATER | 26 HEATER | 27 HEATER |
| CNDSTE PUMPS | DEA STG TK LVL | SEAL STEAM | FWACS SYSTEM | WATER CHEMISTRY | 21 COOL TWR |
| BFBP TEMPS | SUBFP PUMP | FEED PUMP | SPARE PUMP | BFPT ST-SP | 21 SBAC |
| 21 COMPT | 22 COMPT | 23 COMPT | 24 COMPT | 25 COMPT | 26 COMPT |
| 21 FANS | 22 FANS | 21 AIR HTR | 22 AIR HTR | OVERFIRE AIR | LEAK PURGE |
| TURBINE STATUS | DIFF XPANSION | HYDROGEN TEMPS | TURBINE LUBE OIL | CIRC WTR PUMPS | BOILER SEAL AIR |
| 21 SCR | 21 SCR NH3/AIR | 22 SCR | 22 SCR NH3/AIR | SCR AIR COMP | UREA SYSTEM |
| MASTER MENU | TAGOUT MENU | GROUP MENU | SYSTEM STATUS | STRAIN GAUGES | |

Where **i**deas become solutions.



Graphic Changes for the new Temperature Control Design

W1

✓ Select Control Page Zoom Poke Recall 1/4 Help

Econ 21/22 Control GENERATION READINGS Constellation Power Source 2501 BEL ACKNOWLEDGE SCR OPT OFF CUSTOM KEYS 15:39:27 MAY 15, 2007 BRANDON SHORES

Temperature Control Mode

UNIT LOAD 688 M W

IVY/OPTIMIZER STATUS
IVY READY TO ENABLE

SCR Temperature Control

| LOOP | SP MODE SELECT | SP MODE | INLET TEMP | REMIX TEMP | LOOP MODE |
|---------------------|----------------|---------|----------------------|----------------------|----------------------|
| SCR 21 Temp Control | REMIX INLET | REMIX | PV 622.3 SP 619.8 | PV 661.5 SP 660.0 | BYP AUTO OUT AUTO |
| SCR 22 Temp Control | REMIX INLET | REMIX | PV 626.2 SP 619.8 | PV 660.7 SP 660.0 | BYP AUTO OUT AUTO |

SCR Temperature Optimization (IVY) IVY ON IVY OFF STATUS OFF

| LOOP | SP MODE SELECT | SP MODE | WOPF BIAS | IVY BIAS | LOOP MODE |
|--------------------------------|----------------|---------|-----------|----------|-----------|
| 21/22 ID Fan Control | IVY ON IVY OFF | HOLD | 0.50 | 0.54 | AUTO |
| Furnace O ₂ Control | IVY ON IVY OFF | HOLD | 0.01 | -0.05 | AUTO |

IVY SCR OPTIMIZER PERMISSIVES

- IVY PROGRAM READY
- AGR PROGRAM READY
- SCR PATH 21 OPEN
- SCR PATH 22 OPEN
- SCR 21 INLET TEMPS GOOD QUALITY
- SCR 22 INLET TEMPS GOOD QUALITY
- ECON 21 OUTLET REMIX TEMP GOOD QUALITY
- ECON 22 OUTLET REMIX TEMP GOOD QUALITY
- LDC DEMAND OK
- 4 OR MORE COMPTS IN SERVICE
- 21 ID CONTROLLER IN AUTO
- 22 ID CONTROLLER IN AUTO
- FURNACE O₂ CONTROLLER IN AUTO
- BOILER READY

Graphic Changes for the new Temperature Control Design

Select: Remix or
SCR Inlet Mode

Current
Mode indication

Process & Setpoint
Values

Bypass & Outlet Dampers
Auto/Manual

The screenshot shows the SCR Temperature Control HMI interface. At the top, there's a menu bar with 'Select', 'Control', 'Page', 'Zoom', 'Poke', 'Recall', and '1/4'. Below the menu bar, there's a status bar with 'Econ 21/22 Control', 'GENERATION READINGS', 'Constellation Power Source 2501', 'BELL ACKNOWLEDGE', 'SCR OPT OFF', 'CUSTOM KEYS', and a timestamp '15:39:27 MAY 15, 2007 BRANDON SHORES'. The main display area is divided into several sections. On the left, there's a 'UNIT LOAD' display showing '688 M W'. In the center, there's a 'IVY/OPTIMIZER STATUS' display showing 'IVY READY TO ENABLE'. Below these, there's a table for 'SCR Temperature Control' and another for 'SCR Temperature Optimization (IVY)'. On the right, there's a large panel titled 'IVY SCR OPTIMIZER PERMISSIVES' listing various status conditions with green indicator bars. Red callout lines point from the labels at the top to specific elements in the interface: 'Select: Remix or SCR Inlet Mode' points to the 'REMIX' and 'INLET' buttons in the SCR Temperature Control table; 'Current Mode indication' points to the 'REMIX' and 'INLET' buttons in the same table; 'Process & Setpoint Values' points to the 'PV' and 'SP' values in the SCR Temperature Control table; 'Bypass & Outlet Dampers Auto/Manual' points to the 'BYP' and 'OUT' buttons in the SCR Temperature Control table.

| LOOP | SP MODE SELECT | SP MODE | INLET TEMP | REMIK TEMP | LOOP MODE |
|---------------------|----------------|---------|----------------------|----------------------|----------------------|
| SCR 21 Temp Control | REMIX INLET | REMIX | PV 622.3 SP 619.8 | PV 661.5 SP 660.0 | BYP AUTO OUT AUTO |
| SCR 22 Temp Control | REMIX INLET | REMIX | PV 626.2 SP 619.8 | PV 660.7 SP 660.0 | BYP AUTO OUT AUTO |


| LOOP | SP MODE SELECT | SP MODE | WDPC BIAS | IVY BIAS | LOOP MODE |
|--------------------------------|-------------------|---------|-----------|----------|-----------|
| 21/22 ID Fan Control | IVY ON IVY OFF | HOLD | 0.50 | 0.54 | AUTO |
| Furnace O ₂ Control | IVY ON IVY OFF | HOLD | 0.01 | -0.05 | AUTO |

IVY SCR OPTIMIZER PERMISSIVES

- IVY PROGRAM READY
- AGR PROGRAM READY
- SCR PATH 21 OPEN
- SCR PATH 22 OPEN
- SCR 21 INLET TEMPS GOOD QUALITY
- SCR 22 INLET TEMPS GOOD QUALITY
- ECON 21 OUTLET REMIX TEMP GOOD QUALITY
- ECON 22 OUTLET REMIX TEMP GOOD QUALITY
- LDC DEMAND OK
- 4 OR MORE COMPTS IN SERVICE
- 21 ID CONTROLLER IN AUTO
- 22 ID CONTROLLER IN AUTO
- FURNACE O₂ CONTROLLER IN AUTO
- BOILER READY

Graphic Changes for the new Temperature Control Design

Damper Mode Indications: REMIX = Ctrl Remix Temp; INLET = Ctrl SCR Inlet Temp



Where **ideas** become **solutions**.



Remix Temperature Controls: General Tips


- The new DCS controls for the Econ Remix temperature are designed to be used: through the entire load range, year round, and with the SCR in or out of service
 - If remix temperature thermocouple goes *Bad Quality*, an alarm will appear. The recommendation is for operator to go to **Manual** on both dampers
 - Switching to old mode of controlling the SCR inlet temp is an option, but this mode utilizes remix temperature as *Feed-Forward*
- Switching between the old temperature controls and new temperature controls can be done with the dampers in **Auto**.

Note: A small bump may occur since the two modes are controlling slightly different processes.
Ops should monitor dampers while making the switch
- The goal is to remove the old temperature controls at the end of the year

SCR Temperature Optimization

Part #2

Optimization of SCR Inlet Temperatures at Lower Loads (SCR OPT)



Where **i**deas become solutions.




SCR Inlet Temperature Optimization at Lower MW Loads

- The Specific Low Loads: ~350 MW to ~450 MW
- The Goal: Raise SCR Inlet Temperatures at Lower MW Loads to Keep Ammonia System in Service and Raise % Removal of NO_x
- The Method: Calculate and inject optimal bias settings for 2 Ovation DCS control parameters
 1. Bias O₂ Setpoint
Purpose: More Air in Boiler Gives Higher Temperatures. The current range of bias is a 0 – 1.9% increase in O₂
 2. Biases ID Fans
**Purpose: Bring two SCR inlet temperatures closer together to raise
minimum temperature. The current range is 5% of
total bias
(One Fan +2.5% and the Other Fan -2.5%)**

SCR Inlet Temperature Optimization at Lower MW Loads

Ovation DCS Control Modifications




Where **ideas** become **solutions**.

SCR Inlet Temperature Optimization at Lower MW Loads

Ovation DCS Control Modifications

Furnace O2 Control Loop



- **New Optimization Bias Added to O2 Loop**
 - When SCR OPT Optimization System is On and SCR OPT O2 Bias is selected, SCR OPT O2 Bias will be used instead of operator bias
 - Range of Bias is 0-1.9%: Additional air will result in higher SCR inlet temps at lower loads
 - SCR OPT O2 Bias will be removed once load > 450 MW
 - If the operator needs to bias O2 at loads > 450, then the O2 Bias should be removed from the SCR OPT control and the bias should be done as before.
 - When MW load is decreasing at night, the operator should put SCR OPT in control of the O2 bias

Graphic Changes for the new SCR Inlet Temperature Optimization Optimizer Status


The screenshot displays a control system interface with the following components:

- Top Bar:** Includes a menu bar (Select, Control, Page, Zoom, Poke, Recall 1/4) and a status bar (Econ 21/22 Control, GENERATION READINGS, Constellation Power Source 2501, SCR Optimization, 2501, BELL ACKNOWLEDGE, SCR OPT OFF, CUSTOM KEYS, 15:39:27 MAY 15, 2007, BRANDON SHORES).
- Unit Load Display:** Shows UNIT LOAD 688 M W.
- IVY/OPTIMIZER STATUS:** Indicated by a red circle, showing IVY READY TO ENABLE.
- SCR Temperature Control Table:**

| LOOP | SP MODE SELECT | SP MODE | INLET TEMP | REMI X TEMP | LOOP MODE |
|---------------------|-----------------|---------|----------------------|----------------------|----------------------|
| SCR 21 Temp Control | REMI X INLET | REMI X | PV 622.3 SP 619.8 | PV 661.5 SP 660.0 | BYP AUTO OUT AUTO |
| SCR 22 Temp Control | REMI X INLET | REMI X | PV 626.2 SP 619.8 | PV 660.7 SP 660.0 | BYP AUTO OUT AUTO |
- SCR Temperature Optimization (IVY) Table:**

| LOOP | SP MODE SELECT | SP MODE | WDPF BIAS | IVY BIAS | LOOP MODE |
|--------------------------------|-------------------|---------|-----------|----------|-----------|
| 21/22 ID Fan Control | IVY ON IVY OFF | HOLD | 0.50 | 0.54 | AUTO |
| Furnace O ₂ Control | IVY ON IVY OFF | HOLD | 0.01 | -0.05 | AUTO |
- IVY SCR OPTIMIZER PERMISSIVES List:**
 - IVY PROGRAM READY
 - AGR PROGRAM READY
 - SCR PATH 21 OPEN
 - SCR PATH 22 OPEN
 - SCR 21 INLET TEMPS GOOD QUALITY
 - SCR 22 INLET TEMPS GOOD QUALITY
 - ECON 21 OUTLET REMIX TEMP GOOD QUALITY
 - ECON 22 OUTLET REMIX TEMP GOOD QUALITY
 - LDC DEMAND OK
 - 4 OR MORE COMPTS IN SERVICE
 - 21 ID CONTROLLER IN AUTO
 - 22 ID CONTROLLER IN AUTO
 - FURNACE O₂ CONTROLLER IN AUTO
 - BOILER READY

Graphic Changes for the new SCR Inlet Temperature Optimization *Optimizer Status*



- **SCR OPT PROGRAM TROUBLE**
 - SCR OPT Program is Not Running or Aggregates Program is Not Running
 - ACTION: Call Emerson
- **BOILER NOT READY**
 - Boiler Permissives Have Not Been Met for Boiler Optimization
 - ACTION: Check Permissive Window on This Graphic to See Which Permissive is Not Met
- **SCR OPT READY TO ENABLE**
 - All Boiler Permissives Made
 - SCR OPT Programs Are Running
 - SCR OPT Optimization is OFF
- **OPTIMIZER READY**
 - All Boiler Permissives Made
 - SCR OPT Programs Are Running
 - SCR OPT Optimization is ON
 - O2 and ID Fans Are Not in SCR OPT Control
- **OPTIMIZER ON O2 ONLY**
 - All Boiler Permissives Made
 - SCR OPT Programs Are Running
 - SCR OPT Optimization is ON
 - O2 Bias in SCR OPT Control, ID Fan Bias Not in SCR OPT Control
- **OPTIMIZER ON IDS ONLY**
 - All Boiler Permissives Made
 - SCR OPT Programs Are Running
 - SCR OPT Optimization is ON
 - O2 Bias Not In SCR OPT Control, ID Fan Bias In SCR OPT Control
- **OPTIMIZER RUNNING**
 - All Boiler Permissives Made
 - SCR OPT Programs Are Running
 - SCR OPT Optimization is ON
 - O2 Bias In SCR OPT Control, ID Fan Bias In SCR OPT Control

Graphic Changes for the new SCR Inlet Temperature Optimization *Optimizer System Buttons*

The screenshot displays a control system interface with the following components:

- Top Bar:** Includes a menu bar (Select, Control, Page, Zoom, Poke, Recall 1/4) and a status bar with 'W1', 'Econ 21/22 Control', 'GENERATION READINGS', 'Constellation Power Source SCR Optimization 2501', 'BELL ACKNOWLEDGE', 'SCR OPT OFF', 'CUSTOM KEYS', and a timestamp '15:39:27 MAY 15, 2007 BRANDON SHORES'.
- Unit Load Display:** Shows 'UNIT LOAD 688 MW'.
- IVY/OPTIMIZER STATUS:** Displays 'IVY READY TO ENABLE'.
- SCR Temperature Control Table:**

| LOOP | SP MODE SELECT | SP MODE | INLET TEMP | REMIX TEMP | LOOP MODE |
|---------------------|----------------|---------|----------------------|----------------------|----------------------|
| SCR 21 Temp Control | REMIX INLET | REMIX | PV 622.3 SP 619.8 | PV 661.5 SP 660.0 | BYP AUTO OUT AUTO |
| SCR 22 Temp Control | REMIX INLET | REMIX | PV 626.2 SP 619.8 | PV 660.7 SP 660.0 | BYP AUTO OUT AUTO |
- SCR Temperature Optimization (IVY) Section (Highlighted):**

IVY ON IVY OFF STATUS OFF

| LOOP | SP MODE SELECT | SP MODE | WDPF BIAS | IVY BIAS | LOOP MODE |
|--------------------------------|----------------|---------|-----------|----------|-----------|
| 21/22 ID Fan Control | IVY ON IVY OFF | HOLD | 0.50 | 0.54 | AUTO |
| Furnace O ₂ Control | IVY ON IVY OFF | HOLD | 0.01 | -0.05 | AUTO |
- IVY SCR OPTIMIZER PERMISSIVES:**
 - IVY PROGRAM READY
 - AGR PROGRAM READY
 - SCR PATH 21 OPEN
 - SCR PATH 22 OPEN
 - SCR 21 INLET TEMPS GOOD QUALITY
 - SCR 22 INLET TEMPS GOOD QUALITY
 - ECON 21 OUTLET REMIX TEMP GOOD QUALITY
 - ECON 22 OUTLET REMIX TEMP GOOD QUALITY
 - LOC DEMAND OK
 - 4 OR MORE COMPTS IN SERVICE
 - 21 ID CONTROLLER IN AUTO
 - 22 ID CONTROLLER IN AUTO
 - FURNACE O₂ CONTROLLER IN AUTO
 - BOILER READY

Graphic Changes for the new SCR Inlet Temperature Optimization Optimizer System Buttons

Overall SCR OPT Optimization System:

On/Off

| SCR Temperature Optimization (IVY) IVY ON IVY OFF STATUS OFF | | | | | |
|---|--|-------------------|--------------|-------------|-------------------|
| LOOP | SP MODE SELECT | SP MODE | WDPF BIAS | IVY BIAS | LOOP MODE |
| 21/22 ID Fan Control | IVY ON IVY OFF | HOLD | 0.50 | 0.54 | AUTO |
| Furnace O ₂ Control | IVY ON IVY OFF | HOLD | 0.01 | -0.05 | AUTO |

SCR OPT Optimizer - Bias ID Fans
Status

On – Optimize On & controlling ID bias
Off – Optimizer Off & not controlling ID bias
Hold – SCR OPT Optimizer Off, but does have control of ID Bias (if SCR OPT optimizer is turned on, it will have control of ID Bias)

SCR OPT Optimizer - Bias O2
Status

On – Optimize On & controlling O2 bias
Off – Optimizer Off & not controlling O2 bias
Hold – SCR OPT Optimizer Off, but does have control of O2 Bias (if SCR OPT optimizer is turned on, it will have control of O2 Bias)

Where **ideas** become **solutions**.



Graphic Changes for the new SCR Inlet Temperature Optimization *Optimizer System Permissives*

The screenshot displays a control system interface with the following elements:

- Top Bar:** Includes a menu bar (Select, Control, Page, Zoom, Poke, Recall 1/4), a title bar (W1), and a status bar (Help).
- Navigation Bar:** Contains buttons for 'Econ 21/22 Control', 'GENERATION READINGS', 'Constellation Power Source SCR Optimization 2501', 'BELL ACKNOWLEDGE', 'SCR OPT OFF', 'CUSTOM KEYS', and a timestamp '15:39:27 MAY 15, 2007 BRANDON SHORES'.
- Unit Load Display:** Shows 'UNIT LOAD 688 M W'.
- IVY/OPTIMIZER STATUS:** Displays 'IVY READY TO ENABLE'.
- SCR Temperature Control Table:**

| LOOP | SP MODE SELECT | SP MODE | INLET TEMP | REMIX TEMP | LOOP MODE |
|---------------------|----------------|---------|----------------------|----------------------|----------------------|
| SCR 21 Temp Control | REMIX INLET | REMIX | PV 622.3 SP 619.8 | PV 661.5 SP 660.0 | BYP AUTO OUT AUTO |
| SCR 22 Temp Control | REMIX INLET | REMIX | PV 626.2 SP 619.8 | PV 660.7 SP 660.0 | BYP AUTO OUT AUTO |
- SCR Temperature Optimization (IVY) Table:**

| LOOP | SP MODE SELECT | SP MODE | WOPF BIAS | IVY BIAS | LOOP MODE |
|--------------------------------|-------------------|---------|-----------|----------|-----------|
| 21/22 ID Fan Control | IVY ON IVY OFF | HOLD | 0.50 | 0.54 | AUTO |
| Furnace O ₂ Control | IVY ON IVY OFF | HOLD | 0.01 | -0.05 | AUTO |
- IVY SCR OPTIMIZER PERMISSIVES Status Window (Highlighted):**

IVY SCR OPTIMIZER PERMISSIVES

 - IVY PROGRAM READY
 - AGR PROGRAM READY
 - SCR PATH 21 OPEN
 - SCR PATH 22 OPEN
 - SCR 21 INLET TEMPS GOOD QUALITY
 - SCR 22 INLET TEMPS GOOD QUALITY
 - ECON 21 OUTLET REMIX TEMP GOOD QUALITY
 - ECON 22 OUTLET REMIX TEMP GOOD QUALITY
 - LOC DEMAND OK
 - 4 OR MORE COMPTS IN SERVICE
 - 21 ID CONTROLLER IN AUTO
 - 22 ID CONTROLLER IN AUTO
 - FURNACE O₂ CONTROLLER IN AUTO
 - BOILER READY

Graphic Changes for the new SCR Inlet Temperature Optimization Optimizer System Permissives

IVY SCR OPTIMIZER PERMISSIVES

IVY PROGRAM READY
AGR PROGRAM READY
SCR PATH 21 OPEN
SCR PATH 22 OPEN
SCR 21 INLET TEMPS GOOD QUALITY
SCR 22 INLET TEMPS GOOD QUALITY
ECON 21 OUTLET REMIX TEMP GOOD QUALITY
ECON 22 OUTLET REMIX TEMP GOOD QUALITY
LDC DEMAND OK
4 OR MORE COMPTS IN SERVICE
21 ID CONTROLLER IN AUTO
22 ID CONTROLLER IN AUTO
FURNACE O2 CONTROLLER IN AUTO
BOILER READY

- **SCR OPT PROGRAM READY**
 - SCR OPT program is operational
- **AGR PROGRAM READY**
 - AGR program is operational
- **SCR PATH 21 AND 22 OPEN**
 - Both flow paths must be open to turn scr optimization system on
- **SCR 21/22 INLET TEMPS AND 21/22 REMIX TEMPS GOOD QUALITY**
 - Must have good quality on all 4 temperatures for optimization to be on
 - Bad quality on any of the 4 will automatically turn SCR OPT scr optimization off and optimization biases will go to ~0
- **LDC DEMAND OK**
 - LDC demand must be >310 mw to turn optimization system off
 - If demand goes below 310 mw, optimization system will automatically turn off and any optimization biases will go to ~0
- **4 OR MORE COMPS IN SERVICE**
 - SCR OPT SCR optimization system can only be turned on if 4 or more compartments are in service
- **21/22 ID CONTROLLER IN AUTO**
 - 21/22 ID fan controllers must be in AUTO for CRO to enable the ID fan bias for SCR OPT
- **FURNACE O2 CONTROLLER IN AUTO**
 - Furnace O2 controller must be in AUTO for CRO to enable the o2 bias for SCR OPT
- **BOILER READY**
 - Logical AND of permissives 3-8 above. Indicates the boiler is ready for optimization


Graphic Changes for the new SCR Inlet Temperature Optimization *LDC*



Messages are the same as in slide 28
Where **i**deas become **s**olutions.



Graphic Changes for the new SCR Inlet Temperature Optimization *Fan Controls*



SCR Optimization


General Tips

- IVY Should Be On and In Control of Biases of ID Fans and O2
 - High Loads: SCR OPT should not move ID Fans or O2, Optimization Biases should be 0
 - If operator needs control of either at high loads, SCR OPT should be Off for that parameter. Bias the normal way.
 - Once excursion ends, control of that parameter should be returned to SCR OPT (optimization).
- Ramping Unit Down
 - As unit ramps Down, SCR OPT (optimization) will try to control SCR inlet temp to ~580 – 585° F (alarm occurs at 560° F, ammonia trips at 555° F)
 - SCR OPT (optimization) will also try to bring SCR 21 inlet temp and SCR 22 inlet temp closer together
 - Biases will be applied to O2 and ID Fans from SCR OPT (optimization)
 - Make sure SCR OPT is On and Controlling ID Fan Bias and O2 Bias prior to ramp down for maximum effect
- Ramping Unit Up
 - As unit ramps up, SCR OPT (optimization) Biases to O2 and ID Fans should slowly bleed out to a value near 0 as load increases.
 - Unless operator removes optimization control of these Biases, SCR OPT (Optimization) will still have control of Biases

Brandon Unit 1&2 - SCR Inlet Optimization


U1 Gross **677** MW

Unit 1: MW, ID, O2, SCR Inlet



U2 Gross **565** MW

Unit 2: MW, ID, O2, SCR Inlet



Where **ideas** become **solutions**.



Unit 1 SCR Opt Overview

Unit Load **679** MW

IVY/Optimizer Status
BOILER NOT READY

5/27/2008 9:19:08 AM

SCR Temperature Control

| Loop | SP Mode | Inlet Temp | Remix Temp | Loop Mode |
|---------------------|---------|----------------------|----------------------|----------------------|
| SCR 11 Temp Control | Remix | PV 624.2 SP 619.5 | PV 666.2 SP 660.0 | BYP Auto OUT Auto |
| SCR 12 Temp Control | Remix | PV 632.6 SP 619.5 | PV 660.4 SP 660.0 | BYP Auto OUT Auto |

SCR Temperature Optimization (IVY)

Status **OFF**

| Loop | SP Mode | WDPF Bias | IVY Bias | Loop Mode |
|--------------|---------|-----------|----------|-----------|
| 11/12 ID Fan | OFF | -0.12 | -0.518 | Auto |
| Furnace O2 | OFF | 0.01 | -0.057 | Auto |

IVY SCR Optimizer Permissives

| | |
|------------------------------------|-------------------------------------|
| IVY Program Ready | <input checked="" type="checkbox"/> |
| AGR Program Ready | <input checked="" type="checkbox"/> |
| SCR Path 11 Open | <input type="checkbox"/> |
| SCR Path 12 Open | <input type="checkbox"/> |
| SCR 11 Inlet Temps Good Quality | <input checked="" type="checkbox"/> |
| SCR 12 Inlet Temps Good Quality | <input checked="" type="checkbox"/> |
| Econ 11 Out Remix Tmp Good Quality | <input checked="" type="checkbox"/> |
| Econ 12 Out Remix Tmp Good Quality | <input checked="" type="checkbox"/> |
| LDC Demand OK | <input checked="" type="checkbox"/> |
| 4 or More Compts In Service | <input checked="" type="checkbox"/> |
| 11 ID Controller In Auto | <input checked="" type="checkbox"/> |
| 12 ID Controller In Auto | <input checked="" type="checkbox"/> |
| Furnace O2 Controller In Auto | <input checked="" type="checkbox"/> |
| Boiler Ready | <input type="checkbox"/> |

Where **ideas** become **solutions**.



Unit 2 SCR Optimization

Unit Load **575** M
W

IVY/Optimizer Status
IVY READY TO ENABLE

5/27/2008 9:29:08 AM

SCR Temperature Control

| Loop | SP Mode | Inlet Temp | Remix Temp | Loop Mode |
|---------------------|---------|----------------------|----------------------|----------------------|
| SCR 21 Temp Control | Remix | PV 610.2 SP 614.5 | PV 660.2 SP 660.0 | BYP Auto OUT Auto |
| SCR 22 Temp Control | Remix | PV 615.9 SP 614.5 | PV 659.7 SP 660.0 | BYP Auto OUT Auto |

SCR Temperature Optimization (IVY)

Status OFF

| Loop | SP Mode | WDPF Bias | IVY Bias | Loop Mode |
|--------------|---------|-----------|----------|-----------|
| 21/22 ID Fan | OFF | -0.09 | 0.638 | Auto |
| Furnace O2 | OFF | -0.63 | -0.047 | Auto |

IVY SCR Optimizer Permissives

| | |
|------------------------------------|---|
| IVY Program Ready | ■ |
| AGR Program Ready | ■ |
| SCR Path 21 Open | ■ |
| SCR Path 22 Open | ■ |
| SCR 21 Inlet Temps Good Quality | ■ |
| SCR 22 Inlet Temps Good Quality | ■ |
| Econ 21 Out Remix Tmp Good Quality | ■ |
| Econ 22 Out Remix Tmp Good Quality | ■ |
| LDC Demand OK | ■ |
| 4 or More Compts In Service | ■ |
| 21 ID Controller In Auto | ■ |
| 22 ID Controller In Auto | ■ |
| Furnace O2 Controller In Auto | ■ |
| Boiler Ready | ■ |

Where **ideas** become **solutions**.



Years of experience in process control design, implementation, and field installation

With more than 400 SmartProcess installations on many different control systems, Emerson is the market leader in advanced control.

AES Alliant Energy Ameren Energy Generating American
Electric Power Constellation Power Source Generation
Dairyland Power Technology Power
Generators Edison
Mission T.
Kosciuszko Interergy
Louisiana Authority
Keyspan Corporation
(KEPCO) Nevada
Power Public
Service of New Hampshire Saudi Electric Company
Seminole Electric Cooperative Sempra Energy Resources
Southern California Edison University of Michigan We
Energies When Energy becomes a solution. Elektronika Ostroleka, S.A.

