

SmartProcess Distillation Application Improves Recovery and Saves Energy – A Case Study

Pete Sharpe

Director, Industry Solutions for Refining & Chemicals



2009 Emerson Global Users Exchange

Presenters

Pete Sharpe





Agenda

- Operating Challenges
- Project Methodology
- Process Overview
 - Process Flow
 - Operating Objectives
- SmartProcess® Distillation Optimizer
- Results



Operating Challenges

- Purification unit involving multiple distillation trains with 11 columns
- Ultra-high purity product specifications require very tight quality controls
- Multiple large, 200+ tray columns with extremely long time constants
- Large energy consumer
- Different feedstock suppliers with different qualities unloaded from railcars
- Safety margins required to compensate for disturbances in feed quality





Project Methodology

- APC licenses were specified and included as part of the DeltaV migration project
 - Capital expense
- Functional Specification prepared by Emerson that included the design for the complete process unit (11 distillation columns)
- Initial implementation phase covered only the first column in the series
 - Gain customer experience with technology
 - Develop Operator acceptance
 - Demonstrate value to management
- Subsequent phases to be implemented by customer engineers with support from Emerson APC Consultants



Project Implementation

- FDS phase included on-site audit of instrumentation and control strategies and preliminary step tests
 - Identified regulatory control issues that needed to be addressed prior to on-site work
- Software installation of SmartProcess application performed by customer personnel prior to on-site work
- Emerson consultants spent 2 weeks on-site for configuration and commissioning
- Performance improvements estimated and presented to operations management based on initial trial run






Advanced Control Solution

- SmartProcess® Distillation Optimizer
 - Utilizes Embedded DeltaV Advanced Process Control
 - On-Line Key Performance Indicator (KPI) Calculations
- Emerson APC Consulting Services
 - Functional Design
 - Control Performance Audit
 - Implementation Assistance
- Initially started with first column in the train that removes light contaminates




Process Overview



- Column separates components based on different boiling points
- Tray temperatures reflect composition on that tray, but need to be compensated for pressure
- Control strategies based on "What comes in must go out"
 - Material Balance
 - Energy Balance
- Material Balance:
 - OH / Feed Ratio
- Energy Balance:
 - Reflux / Feed Ratio




Distillation Process Affect of Energy



EXCHANGE


2009 Emerson Global Users Exchange

Cost of Variability



APC Optimization

Objective: Minimize overhead product loss while controlling bottoms impurities to target





SmartProcess Applications – Tools vs. Solutions

Products, Services, Expertise

We have the best materials, craft skills, tools, and services. What can we build for you?



ENGAGING MINDS. AMAZING RESULTS. 2009 Emerson Global Users Exchange

Applications

We've developed a variety of houses to meet your specific needs.




What are SmartProcess Applications?

- Re-usable applications that can be pre-engineered and used multiple times
- Combination of:
 - DeltaV composite blocks, modules & templates
 - APC tools (e.g. PredictPro, Neural)
 - DeltaV Graphics
 - Documentation
 - Sample Configuration
 - Simple dynamic simulation







Applications Enable Faster, More Efficient APC Implementations



SmartProcess Distillation Control Module



Standard Operator Display & Simulation



Key Process Variables

- Manipulated Variables (MV) Controller setpoints written to by the MPC.
 - Distillate Rate
 - Reboiler Steam
- Controlled Variables (CV) Process variables which are to be maintained at a specific value; i.e., the setpoint
 - Lower tray Pressure Compensated Temperature (PCT)
 - Overhead PCT
- Disturbance Variables (DV) Measured variables which may also affect the value of controlled variables
 - Feed Flows (2)
 - Reflux Temp
- Constraints (LV) Variables which must be maintained within an operating range (a special type of CV)
 - Overhead product loss (on-line analyzer)
 - Light impurities in bottoms (on-line analyzer)
 - Internal Reflux Rate
 - Column Delta Pressure
 - Reflux/Distillate Ratio





Process Issues


Reboiler steam instability

- Interaction between parallel reboilers with common steam trap, one fouled, one clean. In Manual and Auto, steam flow varied ~10kLb/Hr out of 50. Process design issue.
- Caused ~0.5 Deg F variability in tray temp used as CV
- Overhead pressure controller range
 - Pressure is controlled by two valves in the condenser system, one large and one small
 - OH PIC operates small valve with large valve normally in Manual.
 - Small valve had insufficient range to control between day and night
 - Pressure swings caused changes in temps and qualities
 - Implemented control function to adjust large valve to keep small valve in control range
- Small process gains
 - Issue primarily due to big difference in instrument ranges
 - Solved by using scaler blocks for process inputs






Reboiler Flow Variability






Pressure Effects





Steam Step Tests





Test Compromised due to OH pressure swings






Model Verification








Initial Closed Loop Operation – Small Gains





Initial Controller Results





Summary of Results

- Controller immediately started reducing distillate rate and OH product losses
- Average OH product loss reduced by approximately 22%
- Impurities in Btms were maintained within specifications.
- Steam usage reduced on average around 7%
- Estimated value over \$700k per year



Summary

- High-purity distillation columns offer significant opportunities for improvement from APC
- A SmartProcess® Distillation Optimizer was implemented on a large purification column
- Following the functional design, the project was completed in 2 weeks on-site
- Excellent project payback achieved



Where To Get More Information

TO BE ADDED LATER

